

**VELUX TGC 014 SUN TUNNEL Skylights
LEED 3.0 Recycled Content and Regional Materials Data**

VELUX TGC 014 SUN TUNNEL		Weight of Installed Product (lbs.)	% of Total Weight	MR Credit 4: Recycle Content				MR Credit 5: Regional Materials	
				% Recycled Content by Weight		Recycled Content Weight (lbs.)		Percent Steel Content by Weight	Manufacturing Location
				Pre Consumer	Post Consumer	Pre Consumer	Post Consumer		
1	TGC 014	14.1	100%	2.8%	0.9%	0.39	0.13	46.2%	Greenwood, SC
	Dome	2.9	21%	0.0%	0.0%	0.00	0.00		Greenwood, SC
	Reflective Collar	1.3	9%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Pivot/Intermediate Rings	2.8	20%	2.0%	0.0%	0.28	0.00		Greenwood, SC
	Flashing	6.5	46%	0.3%	0.1%	0.05	0.01	100.0%	Covington, GA
	Hardware	0.6	4%	0.5%	0.8%	0.06	0.12		Taiwan
2	TTK 014	4.3	100%	0.4%	0.8%	0.02	0.03		Greenwood, SC
	Tunnel	1.7	40%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Elbow	2.0	47%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Hardware	0.6	14%	0.4%	0.8%	0.02	0.03		Taiwan
3	TTC 014	9.0	100%	15.9%	6.0%	1.42	0.54		Greenwood, SC
	Diffuser	0.9	10%	1.2%	0.0%	0.11	0.00		Greenwood, SC
	Diffuser Frame	1.2	13%	11.4%	0.0%	1.02	0.00		Taunton, MA
	Ceiling Adapter Assembly	4.0	45%	0.0%	0.0%	0.00	0.00		Greenwood, SC
	Reducer	1.2	13%	0.0%	0.0%	0.00	0.00		Dale, IN
	Hardware	1.7	19%	4.8%	8.7%	0.43	0.78		Taiwan
4	TOC 014	0.8	100%	25.7%	2.7%	0.20	0.02		Greenwood, SC
	OCD Trim ring w/ diffuser	0.7	90%	24.2%	0.0%	0.19	0.00		Greenwood, SC
	Hardware	0.1	13%	1.5%	2.7%	0.01	0.02		Taiwan
5	THC 014	2.9	100%	12.1%	0.0%	0.35	0.00		Greenwood, SC
	Ceiling Ring	1.2	41%	4.6%	0.0%	0.13	0.00		Greenwood, SC
	Trim Ring	0.5	17%	2.6%	0.0%	0.08	0.00		Greenwood, SC
	Diffuser	1.2	41%	5.0%	0.0%	0.14	0.00		Greenwood, SC
6	TGC 014_TTK_TTC Assembled	27.3	100%	7.0%	3.1%	1.91	0.84	23.8%	Greenwood, SC
	Dome	2.9	11%	0.0%	0.0%	0.00	0.00		Greenwood, SC
	Reflective Collar	1.3	5%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Pivot/Intermediate Rings	2.8	10%	1.0%	0.0%	0.28	0.00		Greenwood, SC
	Flashing	6.5	24%	0.2%	0.1%	0.05	0.02	100.0%	Covington, GA
	Tunnel	1.7	6%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Elbow	2.0	7%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Diffuser	0.9	3%	0.4%	0.0%	0.11	0.00		Greenwood, SC
	Diffuser Frame	1.2	4%	3.7%	0.0%	1.02	0.00		Taunton, MA
	Ceiling Adapter Assembly	4.0	15%	0.0%	0.0%	0.00	0.00		Greenwood, SC
	Reducer	1.2	4%	0.0%	0.0%	0.00	0.00		Dale, IN
	Hardware	2.8	10%	1.4%	2.5%	0.38	0.69		Taiwan

VELUX TGC 014 SUN TUNNEL Skylights
LEED 3.0 Recycled Content and Regional Materials Data

VELUX TGC 014 SUN TUNNEL		Weight of Installed Product (lbs.)	% of Total Weight	MR Credit 4: Recycle Content				MR Credit 5: Regional Materials	
				% Recycled Content by Weight		Recycled Content Weight (lbs.)		Percent Steel Content by Weight	Manufacturing Location
				Pre Consumer	Post Consumer	Pre Consumer	Post Consumer		
7	TGC 014_TTK_TOC Assembled	19.1	100%	3.6%	1.5%	0.69	0.28	34.0%	Greenwood, SC
	Dome	2.9	15%	0.0%	0.0%	0.00	0.00		Greenwood, SC
	Reflective Collar	1.3	7%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Pivot/Intermediate Rings	2.8	15%	1.5%	0.0%	0.28	0.00		Greenwood, SC
	Flashing	6.5	34%	0.3%	0.1%	0.05	0.01	100.0%	Covington, GA
	Tunnel	1.7	9%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Elbow	2.0	10%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	OCD Trim ring w/ diffuser	0.7	4%	1.0%	0.0%	0.19	0.00		Greenwood, SC
	Hardware	1.2	6%	0.5%	0.9%	0.10	0.17		Taiwan
8	TGC 014_TTK_THC Assembled	21.2	100%	3.9%	1.3%	0.84	0.27	30.6%	Greenwood, SC
	Dome	2.9	14%	0.0%	0.0%	0.00	0.00		Greenwood, SC
	Reflective Collar	1.3	6%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Pivot/Intermediate Rings	2.8	13%	1.3%	0.0%	0.28	0.00		Greenwood, SC
	Flashing	6.5	31%	0.2%	0.1%	0.05	0.01	100.0%	Covington, GA
	Tunnel	1.7	8%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Elbow	2.0	9%	0.0%	0.0%	0.00	0.00		Lawrenceville, GA
	Ceiling Ring	1.7	8%	0.6%	0.0%	0.13	0.00		Greenwood, SC
	Trim Ring	0.5	2%	0.4%	0.0%	0.07	0.00		Greenwood, SC
	Diffuser	1.2	6%	0.7%	0.0%	0.14	0.00		Greenwood, SC
	Hardware	0.6	3%	0.4%	0.7%	0.08	0.15		Taiwan